

**Dillingham City - Central Administration Roof****FY2001 Request: \$50,250****Reference No: AMD 33574****AP/AL:** Appropriation**Project Type:** Renewal and Replacement**Category:** Education**Location:** Dillingham**Contact:** Karen J. Rehfeld**House District:** Bethel, Dillingham (HD 39)**Contact Phone:** (907)465-8650**Estimated Project Dates:** 07/01/2000 - 06/30/2005**Brief Summary and Statement of Need:**

This project is the FY2001 Major Maintenance Grant Fund Priority #48 and is scheduled to begin in FY2002.

<b>Funding:</b>	<u>FY2001</u>	<u>FY2002</u>	<u>FY2003</u>	<u>FY2004</u>	<u>FY2005</u>	<u>FY2006</u>	<u>Total</u>
AHFC Bonds	\$50,250						\$50,250
<b>Total:</b>	\$50,250	\$0	\$0	\$0	\$0	\$0	\$50,250

<input type="checkbox"/> State Match Required	<input checked="" type="checkbox"/> One-Time Project	<input type="checkbox"/> Phased - new	<input type="checkbox"/> Phased - underway	<input type="checkbox"/> On-Going
0% = Minimum State Match % Required		<input checked="" type="checkbox"/> Amendment	<input type="checkbox"/> Mental Health Bill	

**Operating & Maintenance Costs:**

	<u>Amount</u>	<u>Staff</u>
Project Development:	0	0
Ongoing Operating:	0	0
One-Time Startup:	0	
<b>Totals:</b>	<b>0</b>	<b>0</b>

**Additional Information / Prior Funding History:****Project Description/Justification:**

This project will remove the old 4,500 square foot metal roof, which leaks severely causing interior damage. The roof will be sheeted with 5/8-inch CDX plywood, an ice and water shield, and 60-pound felt. A metal clip-ribbed roof will be installed. Dormers will be sheeted, flashed, and iced, and a water shield membrane will be installed. Roof panels will pass the UL 90 wind lift-up test. A factory-certified installer will install them. Proposed cost: \$71,786.