Mt. Edgecumbe High School Roof Repair and Replacement **FY2002 Request: $600,000**
Reference No: 34116

AP/AL: Appropriation
Project Type: Deferred Maintenance
Category: Education
Location: Sitka
Contact: Karen Rehfeld
House District: Sitka, Wrangell, Petersburg (HD 2)
Contact Phone: (907)465-8650
Estimated Project Dates: 07/01/2001 - 06/30/2006

Brief Summary and Statement of Need:
This project will addresses critical roof repairs and/or replacement in three of the main residential buildings at Mt. Edgecumbe High School. The buildings, all built in the 1940's, include the girls and boys dormitory and the kitchen/dining building. Leaking roofs and the resulting water damage to roof decking and interior walls threaten the structural integrity of these buildings. The supporting timbers must be inspected for rot and replaced if necessary. In addition, the current construction does not meeting the required 1- hour fire code rating.

Funding:	FY2002	FY2003	FY2004	FY2005	FY2006	FY2007	Total
Gen Fund	$600,000						$600,000
Total:	$600,000	$0	$0	$0	$0	$0	$600,000

☐ State Match Required ☑ One-Time Project ☐ Phased - new ☐ Phased - underway ☐ On-Going
0% = Minimum State Match % Required ☐ Amendment ☐ Mental Health Bill

Operating & Maintenance Costs:

	Amount	Staff
Project Development:	0	0
Ongoing Operating:	0	0
One-Time Startup:	0	
Totals:	0	0

Additional Information / Prior Funding History:
No prior year funding has been provided for this request. Mt. Edgecumbe received $214,900 in FY96, $200,000 in FY98 and $150,000 in FY2001 for dormitory repairs, renovation and equipment.

Project Description/Justification:
Roof Replacement Projects $600,000

Girl's Dormitory $250,000
1. Lateral force analysis of roof structure & timber structure inspection
2. Replace roofing shingles with treated
3. Replace gutters & downspouts

Boy's Dormitory $250,000
1. Lateral force analysis of roof structure & timber structure inspection
2. Roof deck timber replacement
3. Replace asphalt shingles with treated
4. Replace gutters & downspouts

Kitchen/Dining $100,000
1. Inspect canopy & roof framing
2. Roof repair including treated shingles

3. Gutters & downspouts
4. Gable end vent screens