

**Parks Highway: Milepost 285 - Julius Creek Bridge**

**FY2006 Request: \$1,000,000**  
**Reference No: 40326**

**AP/AL:** Allocation

**Project Type:** Construction

**Category:** Transportation

**Location:** Anderson

**Contact:** John MacKinnon

**House District:** Denali/University (HD 8)

**Contact Phone:** (907)465-6973

**Estimated Project Dates:** 07/01/2005 - 06/30/2010

**Appropriation:** Surface Transportation Program

**Brief Summary and Statement of Need:**

Replace the existing highway bridge with a new structure. This bridge is located on the Parks Highway between Anderson and Nenana. This project contributes to the Department's Mission by reducing injuries, fatalities and property damage and by improving the mobility of people and goods.

<b>Funding:</b>	<u>FY2006</u>	<u>FY2007</u>	<u>FY2008</u>	<u>FY2009</u>	<u>FY2010</u>	<u>FY2011</u>	<u>Total</u>
Fed Rcpts	\$1,000,000						\$1,000,000
<b>Total:</b>	\$1,000,000	\$0	\$0	\$0	\$0	\$0	\$1,000,000

<input checked="" type="checkbox"/> State Match Required	<input checked="" type="checkbox"/> One-Time Project	<input type="checkbox"/> Phased - new	<input type="checkbox"/> Phased - underway	<input type="checkbox"/> On-Going
9% = Minimum State Match % Required		<input type="checkbox"/> Amendment	<input type="checkbox"/> Mental Health Bill	

**Operating & Maintenance Costs:**

	<u>Amount</u>	<u>Staff</u>
Project Development:	0	0
Ongoing Operating:	0	0
One-Time Startup:	0	
<b>Totals:</b>	<b>0</b>	<b>0</b>

**Additional Information / Prior Funding History:**

None.

**Project Description/Justification:**

The bridge abutments are jacking unevenly causing a severe twist in the bridge top. Vertical pile movement caused three pilings to jack while two remain stable. This has forced two pilings to pull out of the concrete cap. A permanent solution is necessary to stabilize the situation.