Glenn Highway MP 63.5 Erosion Emergency Repairs	**FY2010 Request:**	**$1,125,000**
	Reference No:	**48804**

AP/AL: Allocation   **Project Type:** Construction
Category: Transportation
Location: Central   **Contact:** Frank Richards
House District: Interior Villages (HD 6)   **Contact Phone:** (907)465-3900
Estimated Project Dates: 04/19/2010 - 12/31/2011
Appropriation: Emergency Repairs

Brief Summary and Statement of Need:
The Matanuska River eroded into the roadway embankment approximately 400 feet in length, resulting in a 9-foot vertical drop close to the edge of the highway pavement, within one foot at some locations. Immediate repairs were taken to preserve the integrity of the embankment and save the highway included placement of super sacks at the toe of the embankment to protect it from further erosion. This project contributes to the Department's Mission by reducing injuries, fatalities and property damage and by improving the mobility of people and goods.

Funding:	FY2010	FY2011	FY2012	FY2013	FY2014	FY2015	Total
Gen Fund	$1,125,000						$1,125,000
Total:	$1,125,000	$0	$0	$0	$0	$0	$1,125,000

☐ State Match Required ☑ One-Time Project	☐ Phased - new	☐ Phased - underway ☐ On-Going
0% = Minimum State Match % Required	☐ Amendment	☐ Mental Health Bill

Operating & Maintenance Costs:

	Amount	Staff
Project Development:	0	0
Ongoing Operating:	0	0
One-Time Startup:	0	
Totals:	0	0

Additional Information / Prior Funding History:
None.

Project Description/Justification:
Permanent repairs will include removal of temporary shore protection, removal of existing guardrail, and installation of new embankment and riprap rock armor for approximately 530 linear feet and installation of new guardrail. A project of this size and costs cannot be absorbed within the existing budget.