

**Agency: Commerce, Community and Economic Development****Grants to Municipalities (AS 37.05.315)****Grant Recipient: Dillingham****Federal Tax ID: 92-0030674****Project Title:****Project Type: Remodel, Reconstruction and Upgrades**

# Dillingham - Wastewater Treatment Plant Upgrades

**State Funding Requested: \$2,280,000****House District: 37 / S**

One-Time Need

**Brief Project Description:**

Upgrade the Dillingham wastewater treatment plant to bring it back into compliance with state standards for its effluent discharge.

**Funding Plan:**

Total Project Cost:	\$13,200,000
Funding Already Secured:	(\$0)
FY2013 State Funding Request:	(\$2,280,000)
Project Deficit:	\$10,920,000

*Funding Details:*

We will be seeking additional funding from ADEC, AIDEA, and AEA for construction and the green components of this overall renovation and upgrade. If we are able to secure the amount of funding needed to bring the system into compliance we do not anticipate requesting more funding.

**Detailed Project Description and Justification:****DESCRIPTION:**

The reason the City of Dillingham has a large capital request for infrastructure is in part due to its own funding base. The City's operating budget is about 7 million dollars. The city currently manages about 35 grants, plus taxes from real and personal property (13 mills each), gaming (10%), alcohol (10%), sales (6%) and overnight stays (10%). However, the taxable land base in the City of Dillingham consists of 13% of the 21,232 acres, or a total of 4.45 square miles of taxable land out of 33 sq. mi. presently within City boundaries.

The project is to complete design and construction of the following upgrades to the City of Dillingham wastewater treatment facility: improvements to the influent debris removal, sludge removal, lagoon wastewater temperature, and additional high efficiency aeration blowers; as well as improvements for lagoon heat retention, including a cover for the lagoon, secondary sludge removal, de-nitrification process, disinfection system, SCADA Controls, and energy extraction.

The proposed improvements will provide a complete automated biological treatment process, with energy recovery (green renewable energy source). The energy recovery process will consist of bio-digesters that use the sludge and local biomass (fish processing and other biomass waste) to create enough heat and electricity through the co-generation process to power and heat the treatment plant operations.

Justification: For years wastewater and ADEC inspections have documented overages in the total amount of effluent as well as higher than permitted levels of fecal coliforme, total suspended solids and increase levels of biochemical oxygen

demand. This is likely due to 3 factors:

1) inadequate size for the population demand that occurs during peak summer season; 2) no cover over the lagoon to help retain heat and keep the system working; and 3) lack of septage handling facilities to dilute the septage and remove garbage from the system.

1) The current treatment lagoon was constructed and permitted in 1987 for 273,000 gallons per day. As such it is completely inadequate to handle the amount of sewage that occurs during peak summer season when Dillingham's population triples, producing approximately 700-900,000 gallons per day.

2) During winter, sewage and sludge settle to the bottom of the lagoon until temperatures are warm enough to reactivate the lagoons' biological processes during late spring. The increase in temperatures creates a temperature inversion, foul odors and severe operational issues occur. Health and safety risk during this period of time, are at a peak, especially with the added population that occurs during this time.

The effluent leaves the outfall just beyond the beach at Snag Point, where residents set nets to catch salmon for home use. There has been no sludge removal over the last 20 years and there is no disinfection of the sewage in the lagoon, thus the effluent frequently exceeds permitted levels of toxins at volumes that also exceed permitted levels and is a health risk for humans and animals.

3) Most of the population growth in Dillingham has and will likely occur off of the existing sewage system. The high water table and poor soils mean that septic systems in certain areas fail regularly and must be pumped. The septage is deposited in the lagoon where it overwhelms the aeration system with sludge and garbage.

The ADEC drafted a Compliance Order in 2008 but never executed it. The City has had numerous inspections showing fecal coliforme counts and total suspended solids exceeding permitted levels in the effluent discharge. In December 2009 ADEC inspected the Dillingham Wastwater Treatment Facility and made a number of recommendations to achieve compliance.

The system can not be permitted until the facility and its discharge meet state standards.

### Project Timeline:

RFP July 1 - August 1, 2012  
 Award Contract August 2, 2012  
 Design and Permitting by December 31, 2012  
 Bid Documents by January 31, 2013  
 Additional Funding secured by February 2013  
 Award Contract by June 1, 2013  
 Construction Complete by September 30, 2013  
 Operation Initiation by October 1, 2013

Construct  
 sludge dewatering pad August 2011  
 construct

**Entity Responsible for the Ongoing Operation and Maintenance of this Project:**

City of Dillingham, Public Works Department, Director Carter Cole

**Grant Recipient Contact Information:**

Name: Jody Seitz  
Title: Planning Director  
Address: Box 889  
Dillingham, Alaska 99576  
Phone Number: (907)842-3785  
Email: planner@dillinghamak.us

Has this project been through a public review process at the local level and is it a community priority?  Yes  No

# FINAL WASTEWATER TREATMENT PLANT STUDY

## CITY OF DILLINGHAM

### Dillingham, Alaska

### Bristol Project No. 210081

### MAY 2010

Prepared for:



111 W. 16<sup>th</sup> Avenue, Third Floor

Anchorage, Alaska 99501-5109

Phone (907) 563-0013

Fax (907) 563-6713



## TABLE OF CONTENTS

<b><u>SECTION</u></b>	<b><u>PAGE</u></b>
ACRONYMS AND ABBREVIATIONS .....	iii
EXECUTIVE SUMMARY .....	ES-1
1.0 INTRODUCTION .....	1
2.0 BACKGROUND .....	3
2.1 Location .....	3
2.2 Community Involvement .....	4
2.3 Existing Conditions.....	4
3.0 DESIGN REQUIREMENTS AND CONSIDERATIONS.....	5
3.1 Regulatory.....	5
3.2 Geotechnical .....	5
3.3 Site Civil .....	5
3.4 Survey .....	5
3.5 Mechanical / Electrical .....	6
4.0 WASTEWATER SYSTEM IMPROVEMENTS .....	7
4.1 Wastewater Treatment Plant Upgrades.....	7
4.1.1 Influent System .....	8
4.1.2 Air Supply .....	9
4.1.3 Aeration System.....	9
4.1.4 Flow Paths.....	10
4.1.5 Disinfection System.....	10
4.1.6 Effluent System.....	11
4.2 Existing Sewage Cell Maintenance .....	11
4.2.1 Background.....	11
4.2.2 Sludge Dewatering.....	12
4.2.3 Solids Disposal.....	12
4.3 Septage Sludge Disposal from Pumper Trucks .....	12
4.3.1 Background.....	12
4.3.2 Disposal Facility at Current Location .....	13
4.3.3 Septage Monofill.....	13
4.4 Permit and Approval Requirements.....	13

4.5	Costs.....	14
4.5.1	Capital Costs .....	14
4.5.2	Operation and Maintenance Costs .....	15
4.6	Conclusions and Recommendations .....	15
5.0	REFERENCES .....	16

## FIGURES

Figure 1	Location and Vicinity Map
Figure 2	Sewage Treatment Facility Improvements – Cover Sheet
Figure 3	Sewage Treatment Facility Improvements – Facility Site Plan
Figure 4	Sewage Treatment Facility Improvements – Lagoon Piping
Figure 5	Sewage Treatment Facility As-Built – Lagoon Yard Piping Plan
Figure 6	Sewage Treatment Facility As-Built – Lagoon and Access Road Site Plan
Figure 7	Sludge Dewatering Pad – Layout
Figure 8	Sludge Dewatering Pad – Details
Figure 9	Proposed Septage Monofill Location
Figure 10	Proposed Septage Monofill Details

## APPENDICES

Appendix A	ADEC Inspection Report (December 2009)
Appendix B	Preliminary Engineers Estimate’s
Appendix C	USACE Memorandum of Snag Point Bank Stabilization Inspection

## ACRONYMS AND ABBREVIATIONS

°	degrees
ADEC	Alaska Department of Environmental Conservation
APDES	Alaska Pollutant Discharge Elimination System
BOD	biochemical oxygen demand
Bristol	Bristol Environmental & Engineering Services Corporation
COBC	Compliance Order by Consent
City	City of Dillingham
DAR	Design Analysis Report
EPA	U.S. Environmental Protection Agency
FC	fecal coliform
O&M	operations and maintenance
TSS	total suspended solids
USACE	US Army Corps of Engineers
WWTP	wastewater treatment plant

(Intentionally blank)

## EXECUTIVE SUMMARY

This plan and recommendations were prepared by Bristol Environmental & Engineering Services Corporation (Bristol) for the City of Dillingham (City) to address needed maintenance and capital upgrades to the community wastewater treatment infrastructure. The plan addresses upgrades to the wastewater treatment plant (WWTP), maintenance of the sewage cells and the addition of a septage monofill at the City landfill. The existing WWTP and sewage cells, were constructed in 1987.

In 2008, the City was notified that it was under a “Compliance Order by Consent” by the Alaska Department of Environmental Conservation (ADEC) for the WWTP effluent discharge. In November 2008, ADEC notified the City that the Compliance Order was “not in effect”, as the wastewater discharge permit renewal had not been finalized (which could impact future treatment levels). In December 2009, ADEC performed an Alaska Pollutant Discharge Elimination System inspection of the WWTP (copy attached as Appendix A). This inspection directed the City to prepare a plan and to work with ADEC to:

- Undertake a baseline parameter sampling program (biochemical oxygen demand total suspended solids, fecal coliform, flow and pH) with regular monitoring and reporting;
- Prepare a Quality Assurance Plan for monitoring and operations; and
- Start a review of the current WWTP operations, and develop a plan to “reduce the chronic nature of ongoing water quality violations. This plan could include 1) moving the septic dumping site, 2) aerating dead spots, 3) installing baffles, 4) removing sludge/solids, 5) adding disinfection, and 6) any other appropriate measures the City sees fit.”

Currently, the two existing sewage cells are overloaded with solids from over 22 years of use without removal. The former operator, Mr. Gary Sharrett, did a series of sludge depth measurements in September 2009 (refer to Section 4.2 for more details). A planned sludge disposal pond was never constructed. As a first and immediate step, the sludge should be removed from the cells, dewatered through using “geotubes”, and then transported to the landfill for permanent disposal.

The next step after sludge removal is to eliminate the direct discharge of septic pumping trucks into the lagoon. Bristol recommends that a septage monofill be constructed at the City landfill for year-round access by septic pumping trucks.

The system should be allowed to operate for a minimum of six-months after solids removal and the elimination of the septic discharge from pumping trucks. After the six-month period, a full evaluation of the system should occur, including a very specific sampling and testing program of the treatment processes and systems.

## **1.0 INTRODUCTION**

This report and recommendations were prepared by Bristol Environmental & Engineering Services Corporation (Bristol) for the City of Dillingham (City) to address existing problems, and recommended improvements of the wastewater treatment plant (WWTP). The City retained Bristol in February 2010 to prepare the report. The report specifically addresses possible upgrades to the WWTP, solids removal and disposal from the sewage cells, and the options for septage disposal from pumper trucks. Future improvements to the headworks, plant piping, the aeration system, possible baffling, and potential disinfection facilities, should be addressed after the solids have been removed and septic disposal has been stopped at the WWTP.

(Intentionally blank)

## 2.0 BACKGROUND

In 2008, the City was notified by the Alaska Department of Environmental Conservation (ADEC) that it was under a “Compliance Order by Consent” (COCB) for the effluent discharge of the WWTP. In November, ADEC notified the City that the COCB was “not in effect” as the wastewater discharge permit renewal has not been finalized (which could impact future treatment levels). Although the COCB was not put in force immediately, the City was directed to do a better job of sampling, testing, and reporting, and to start a review of the current facilities. The results of the recent ADEC APDES inspection in December 2009 specifically directed the City to work with ADEC to:

- Undertake a baseline parameter sampling program (biochemical oxygen demand [BOD]/total suspended solids [TSS], fecal coliform [FC], flow and pH) with regular monitoring and reporting;
- Provide required permit and operations and maintenance (O&M) information at the WWTP;
- Prepare a Quality Assurance Plan for the sampling and operations;
- Review the WWTP operations, and prepare a Plan and Recommendations to address:
  - Headworks
  - Plant piping
  - Solids removal – from the cells
  - Stop direct septic disposal at the WWTP cells
  - Adequacy of the aeration system – and correct any zones with solids deposition
  - Possibly provide baffles to prevent short-circuiting
  - Potential need for disinfection (chlorination – dechlorination) to meet discharge FC limits.

In order to fund the necessary improvements, the City will need to work with ADEC municipal grants and loans, Alaska Native Tribal Health Consortium (under the Sanitation Deficiency System program) and other agencies. The cycle of grant applications is coming up soon (June 2010 for ADEC). This report is also intended to provide needed background for funding.

## 2.1 LOCATION

Dillingham is located at the extreme northern end of Nushagak Bay, in northern Bristol Bay, at the confluence of the Wood and Nushagak rivers. It lies at approximately 59.04 degrees (°)

north latitude and -158.46° west longitude (Section 21, Township 013 South, Range 055 West, Seward Meridian), 300 miles southwest of Anchorage (Figure 1). Dillingham is the economic, transportation, and public service center for western Bristol Bay. Commercial fishing, fish processing, cold storage, and support of the fishing industry are the primary private sector activities. During late spring and summer, the population can double due to fishing. The City's role as the regional center for government and services helps to stabilize seasonal employment (Alaska Department of Community, Commerce, and Economic Development, 2010).

## **2.2 COMMUNITY INVOLVEMENT**

The WWTP issue has been addressed at several recent City Council meetings.

## **2.3 EXISTING CONDITIONS**

Information about the existing conditions at the WWTP, sewage cells, and community landfill are based on previous work performed by Bristol, in the general vicinity, and as-built drawings (1986) for the WWTP proper. No additional geotechnical or survey data was provided for this report.

### **3.0 DESIGN REQUIREMENTS AND CONSIDERATIONS**

The following sections provide a discussion for the proposed upgrades to the WWTP, solids removal and disposal from the sewage cells, and the disposal of septage from local pumper trucks.

#### **3.1 REGULATORY**

Anticipated regulatory requirements include:

- Meeting the intent of a Plan and Recommendations per the December 2009 ADEC APDES Inspection report;
- Compliance with ADEC wastewater regulations: Plan review and approval will be required for the improvements to the WWTP, solids removal program, and the construction of the septage monofill;
- Compliance with ADEC solid waste regulations: Approval will be required for the disposal of solids at the landfill and the construction of the septage monofill;
- Other permits listed in Section 4.4.

#### **3.2 GEOTECHNICAL**

Prior to the design and construction of the septage monofill at the landfill, a geotechnical investigation will be required to determine the depth of groundwater and nature of the soils. No geotechnical work will be required for most of the potential upgrades to the WWTP or the sludge removal from the lagoons. However, if a major disinfection facility is required in the future, site-specific soils investigations will be needed.

#### **3.3 SITE CIVIL**

Civil site design and construction will be required for both the sludge removal from the lagoons and the establishment of a septage monofill at the landfill. Future actions (based on WWTP operations following solids removal) may require significant civil design.

#### **3.4 SURVEY**

Prior to the design of the septage monofill at the landfill, a design survey will need to be completed. No survey is anticipated for the future potential WWTP improvements.

### **3.5 MECHANICAL / ELECTRICAL**

The upgrades to the WWTP may require mechanical and electrical controls design, and associated construction activities.

## **4.0 WASTEWATER SYSTEM IMPROVEMENTS**

### **4.1 WASTEWATER TREATMENT PLANT UPGRADES**

Refer to Figures 2 through 6 for details of the WWTP. Currently the two existing sewage cells are overloaded with solids from over 22 years of use without removal. Because of the current excess sludge conditions and direct septic discharge (in Cell #1), a full evaluation of the system cannot occur. A planned sludge disposal pond was never constructed. The primary concern that the City is now dealing with is the level of Fecal Coliform (FC) bacteria that are being discharged in the effluent. The BOD and TSS levels are generally in compliance, but there have been violations. The volume of sludge buildup in the first lagoon, Cell 1 (currently aerated), appears to be a major problem and could be directly affecting the FC levels. Cell 2 currently serves as the polishing pond – but it also has major sludge buildup (refer to Section 4.2.2).

As a first and immediate step, the sludge should be removed from the cells, dewatered using geotubes, and then transported to the landfill for permanent disposal after at least one freeze-thaw cycle. The next step after sludge removal is to eliminate the direct discharge of septic pumping trucks into the lagoon. Bristol recommends that a septage monofill be constructed at the City landfill for septic pumping trucks.

The system should be allowed to operate for a minimum of six-months after solids removal and the elimination of the septic discharge from pumping trucks. After the six-month period, a full evaluation of the system can occur. At the end of the six-month “initial operations period”, a full program of sampling and testing should be undertaken to determine the adequacy of the WWTP systems components. The existing WWTP contains six distinct systems that will be evaluated to determine if they are functioning efficiently, which are;

- Headworks
- Plant piping
- Aeration system – including piping, diffusers, and blower capacity
- Flow paths (are baffles needed)
- Disinfection
- Influent system
- Effluent discharge system.

#### **4.1.1 Influent System**

##### **4.1.1.1 Existing System**

The main influent system originates at the City dock lift station, which feeds a 10-inch ductile iron force main. The force main discharges through a magnetic flow meter to an inlet diversion box. A second source of influent is the Snag Point force main, which feeds the headworks via a connection to the old septic dump lift station next to the blower building. The inlet diversion box allows for the isolation of flow into Cell 1, Cell 2, or both. Since the WWTP has not operated in any other mode than what is currently in use, the ability to redirect flow is unknown, and several of the control valves are reportedly inoperable. Sewage was intended to be moved from the diversion box to the cells via a 10-inch ductile iron gravity system.

During a site visit by the US Army Corps of Engineers, which were inspecting the Snag Point Bulkhead, it was discovered that the 10-inch force main from the City dock lift station was exposed in two areas (Appendix C). The length of pipe exposed is 19-feet in one area and approximately 63 feet in the other area. These measurements were recorded at the time of the site visit (September 21, 2009). The original construction plans for the force main required a minimum cover of 10-feet.

##### **4.1.1.2 Potential Upgrades**

The WWTP operator previously indicated that there was an overflow problem with the influent system due to high solids buildup in Cell 1. To ensure that the system continues to operate correctly, the City may consider inspecting and possibly replacing the existing gate valves and the magnetic flow meter. The need for a possible future screen and/or grit chamber could be addressed after the solids have been removed from the cells.

The City should address the exposed force main. Possible solutions would be to engineer a protective cover, which would limit the erosion of cover material. Another option would be to excavate and relocate the force main into a deeper trench to provide the 10-feet of cover required by the construction plans.

## **4.1.2 Air Supply**

### **4.1.2.1 Existing System**

Four (4) Sutorbuilt (7MVF) rotary positive blowers powered by 25-horsepower electric motors provide the air supply for the aeration system. Manufacturer's literature indicates that the blowers are capable of producing 700 to 1300 cubic feet per minute of air volume. The manufacturer's representative indicated the existing blowers have a useful life of 30 years if properly maintained. One of the blowers was off-line at the time of the history report prepared by Mr. Gary Sharrett.

### **4.1.2.2 Potential Upgrades**

As an interim measure, the drive belts on the blowers should be replaced. Due to the age of the existing blowers, the City should plan to replace all the blowers with new, high-efficiency models as part of the future WWTP modifications.

## **4.1.3 Aeration System**

### **4.1.3.1 Existing System**

Air is fed through 8-inch ductile iron headers into 4-inch polyethylene lines, and then into the diffuser tubes. Butterfly valves are used to adjust the airflow to each run. Each cell contains 31 static diffusers arranged in a grid pattern. The WWTP operator indicates that air is injected into Cell 1 only, and Cell 2 is a polishing pond. Refer to Figures 4 and 5 for details of the existing aeration system.

### **4.1.3.2 Potential Upgrades**

The WWTP operator recommends that 10 air line valves be replaced. The majority of the valves have not been properly exercised and maintained. If it is determined that the aeration system was not operating properly following the sludge removal, the following may be considered for improving the system: resize and replace the header and aeration piping (based on new blower configurations), replace the static diffusers with new technology, and replace the header control valves. If any "dead zones" are identified after solids removal, either an expansion of the diffusers systems or installation of submersible mixers is recommended.

#### **4.1.4 Flow Paths**

##### **4.1.4.1 Existing System**

The sewage enters the lagoon through the inlet diversion box. For the past 22 years, the sewage flow enters in Cell 1 and flows to Cell 2 before being discharged. No direct sewage is discharged into Cell 2. It is unclear how much retention time is associated with each lagoon before effluent waste is discharged.

##### **4.1.4.2 Potential Upgrades**

If the flow paths within the system appear to “short-circuit”, or were determined to be inadequate after the solids have been removed, the following could be considered to improve the flow of the system: install baffles, resize piping, or install submersible mixers (refer to 4.1.3.2 above). The baffles would prevent short-circuiting of the system and maximize oxygen transfer. The submersible mixers would increase solids suspension, prevent dead spots, and increase treatment efficiency.

#### **4.1.5 Disinfection System**

##### **4.1.5.1 Existing System**

No disinfection is currently provided.

##### **4.1.5.2 Potential Upgrades**

The issue of needing disinfection of the effluent (most likely chlorination followed by de-chlorination to tie up the free chlorine products, to reduce the impacts to the anadromous fishery) will be decided after the sludge is removed and alternative septic dumping is provided, along with making other operational changes to better manage the WWTP process. If disinfection is ultimately determined to be needed, it will be an expensive and labor-intensive requirement added to the WWTP operations. Available records should be reviewed from the 1980s and 1990s to determine what the effluent characteristics were prior to the excessive sludge buildup.

#### **4.1.6 Effluent System**

##### **4.1.6.1 Existing System**

Effluent is directed from either Cell 1 or Cell 2 via a 10-inch ductile iron pipe that terminates in overflow control sumps. The WWTP has always operated with the effluent discharging from Cell 2. A 12-inch ductile iron gravity system discharges from the sumps into Nushagak Bay (via a 12-inch HDPE anchored outfall).

During a site visit by the US Army Corps of Engineers, which were inspecting the Snag Point Bulkhead, it was discovered that the 12-inch gravity discharge from the WWTP was exposed. The exposed length of pipe at the time of the site visit (September 21, 2009) was approximately 37 feet. The original construction plans required a minimum cover of 10 feet.

##### **4.1.6.2 Potential Upgrades**

Existing gate valves and 8-inch plug valves within the overflow sumps probably need to be replaced.

The City should address the exposed discharge. Possible solutions would be to engineer a protective cover, which would limit the erosion of cover material. Another option would be to excavate and relocate the force main into a deeper trench to provide the 10 feet of cover required by the construction plans.

#### **4.2 EXISTING SEWAGE CELL MAINTENANCE**

##### **4.2.1 Background**

A sludge blanket (solids) survey of the sewage cells was performed by the City in September of 2009. The sludge depth in Cells 1 and 2 vary from 1.5 feet to 6.0 feet deep. Bristol performed calculations based on the City's data and determined that Cell 1 contains 5,000 cubic yards (1.01 million gallons) and Cell 2 contains approximately 5,500 cubic yards (1.11 million gallons) of sludge. It is Bristol's opinion that the most pressing issue is to remove this sludge from the cells. Once the sludge is removed from the cells, it is anticipated that the volume will increase by as much as 50%, resulting in a total hydraulic volume for Cell 1 and 2 of 3.18 million gallons. Bristol is proposing an on-site, freeze-thaw dewatering process to decrease the total volume of material to be transported and hauled to the City landfill due to the large volume of sludge.

#### **4.2.2 Sludge Dewatering**

To accomplish the sludge dewatering, a 263-foot by 253-foot pad would be constructed near the existing cells (see Figures 6 and 7). The pad would be designed and constructed for continual use throughout the remaining life of the WWTP. Sludge would be pumped from the cells into 15-foot by 100-foot geotubes, which would be allowed to go through at least one complete freeze-thaw cycle before the solids are transported to the landfill for disposal. The geotubes would be destroyed after one use. The dewatering pad will be sized so that it can accommodate up to 24 geotubes. Based on a recent conversation with one potential sludge removal contractor, sludge removal for both ponds would take two summers of work.

#### **4.2.3 Solids Disposal**

Once the sludge is dewatered, the sludge can be hauled and disposed of at the City landfill. Special containment will not be required if the sludge passes a Paint Filter Liquids Test (U.S. Environmental Protection Agency [EPA] Method 9095) and is free from pathogens as defined by EPA part 503. It is assumed that the dewatering method above will allow the sludge to pass the Paint Filter Test. Common methods used for ensuring the sludge is free of pathogens are to incinerate the waste or to apply lime until the waste has a high pH (greater than pH11). The sludge disposed of at the landfill should be covered daily to isolate the sludge from environmental factors. Disposal of the solids requires coordination with the ADEC Solid Waste Group and the City landfill operator.

### **4.3 SEPTAGE SLUDGE DISPOSAL FROM PUMPER TRUCKS**

#### **4.3.1 Background**

Cell 1 is currently the septage sludge disposal point for local septage pumper trucks. The trucks discharge directly into the northwest corner of Cell 1. The direct insertion of solids into the cell is attributing to an increase in the amount of solids within the system; therefore, causing the solids content to increase faster than it would otherwise. It is estimated that approximately 1,100 cubic yards (222,000 gallons) of septage solids from pumper trucks are disposed of in the cell each year. Bristol looked at two possible solutions for septage disposal, either a disposal system at the WWTP or a new septage monofill at the City landfill.

### **4.3.2 Disposal Facility at Current Location**

In order to regulate the rate and location at which septage is placed in the cell, a possible solution would be to construct a septage holding tank with a variable speed macerator pump. The proposed system should be placed to allow easy and safe access for disposal trucks. A possible location would be to utilize an area on the dewatering pad once the dewatering is completed. Based on preliminary engineering, the system would require a 5,000-gallon tank, 3-horsepower macerator pump (3-inch outlet), and associated valves and piping to reach the cells. This system should be designed and constructed to provide year round use.

### **4.3.3 Septage Monofill**

Another disposal option for septage pumper trucks would be to construct a year-round access septage monofill at the City landfill. The monofill should be constructed where surface run-off will not be directed to the active landfill cell. A possible location for the monofill is shown on Figure 9. This location was chosen due to its distance from the current open cell and the possibility of a lower groundwater table when compared to the current open cell's groundwater level.

Typical layout details for the monofill are shown on Figure 10. Based on preliminary engineering estimates, approximately 450 lineal feet of trench would be required per year to accommodate the septage disposal of pumper trucks. The area shown on Figure 9 would have approximately seven years of useful life, assuming the septage disposal rate does not increase. After the monofill has been backfilled and the septage stabilized, the area could potentially be used for a new solid waste cell or inert waste disposal.

## **4.4 PERMIT AND APPROVAL REQUIREMENTS**

Detailed plans and specifications will need to be developed for any modifications to the current WWTP system. The ADEC will need to issue both an approval to construct and approval to operate. The following permits and agency coordination will be required at a minimum:

- An ADEC Storm Water Pollution and Prevention Plan for the construction of the dewatering pad;
- U.S. Army Corps of Engineers Section 404 placement of fill in wetlands;

- Coastal project questionnaire;
- City of Dillingham land use permit;
- ADEC Wastewater division plan approval;
  - Sludge dewatering pad
  - Septage monofill
  - Approval for WWTP upgrades or modifications
  - Interim APDES permit allowances during solids removal and future WWTP upgrades
- ADEC Solid waste division;
  - Approval for solids disposal
  - Landfills general permit modification for monofill.

## 4.5 COSTS

### 4.5.1 Capital Costs

The estimated capital costs for the proposed improvements are shown below. Detailed cost estimates are provided as Appendix B.

• Upgrades to the WWTP	<b>(To be determined)</b>
• Sludge Dewatering Pad	<b>\$550,000</b>
• Removal of sludge Cells 1 and 2	<b>\$ 600,000</b>
• Septage Disposal Station at WWTP	<b>\$210,000</b>
• Septage Monofill	<b>\$370,000</b>

These estimates assume that all equipment and labor will be provided locally.

#### 4.5.2 Operation and Maintenance Costs

The annual O&M costs for the proposed improvements are estimated below.

- |                                    |                           |
|------------------------------------|---------------------------|
| • Upgrades to the WWTP             | <b>(To be determined)</b> |
| • Sludge Dewatering Pad            | <b>(N/A)</b>              |
| • Septage Disposal Station at WWTP | <b>\$20,000</b>           |
| • Septage Monofill                 | <b>\$18,000</b>           |

#### 4.6 CONCLUSIONS AND RECOMMENDATIONS

Based on Bristol's evaluation of the WWTP system, the following should be implemented in order.

1. Evaluate repair options for exposed force main and outfall.
2. Construct the dewatering pad.
3. Construct the septage monofill at the landfill.
  - a. This is a better long-term solution than septage disposal at the WWTP.
4. Disallow septage disposal from pumper trucks directly into the system.
5. Remove sludge from Cells 1 and 2. This process will take over two years.
6. Dispose of solids at the landfill.
7. Evaluate the effectiveness of the WWTP system after the removal of the sludge and system has been allowed to operate for three months. Provide for a thorough sampling and testing program to determine actual WWTP operations.
8. Design upgrades to the WWTP based on the evaluation to operate within ADEC guidelines.
9. Construct upgrades to the WWTP system.

## 5.0 REFERENCES

- Alaska Department of Commerce, Community and Economic Development, 2010. Alaska Community Database, Detailed Query. Website: [http://www.dced.state.ak.us/dca/commdb/CF\\_BLOCK.cfm](http://www.dced.state.ak.us/dca/commdb/CF_BLOCK.cfm). Accessed April 2010.
- U.S. Environmental Protection Agency. *Process Design Manual – Surface Disposal of Sewage Sludge and Domestic Sludge*. EPA/625/K-95/002. September 1995.
- CEPOA-EN-HH (1105-2-10b), Memorandum Thru CEPOA-EN-CH-HH (Eisses) For the Record, Subject: Inspection of Completed Works, Dillingham Bank Stabilization, Snag Point Bulkhead, Dillingham, Alaska 21 September 2009; Issued 2/18/2010.

(Intentionally blank)



## **FIGURES**



Drawing: K:\JOBS\210081\_WWTP\_STUDY\ACAD-DESIGN\FEASIBILITY\210081\_FIG\_1.DWG - Layout: FIG1  
 User: MHIMLER May 06, 2010 - 8:32am Xrefs: BR\_85X1IP.DWG - Images: DILLINGHAM\_A7.TIF



**PRELIMINARY DESIGN**





**FIGURE 1  
 DILLINGHAM, ALASKA  
 WASTE WATER TREATMENT PLANT STUDY  
 LOCATION AND VICINITY MAP**

**Bristol**  
 ENVIRONMENTAL & ENGINEERING  
 SERVICES CORPORATION  
 Phone (907) 563-0013 Fax (907) 563-6713

DATUM:	DATE	SHEET
N/A	APRIL 2010	
PROJECTION:	DWN.	1
NONE	IPP	
	SCALE	of
	SHOWN	
	APPRVD.	10
	TMW	



# SEWAGE TREATMENT FACILITY IMPROVEMENTS



**PELIMINARY**  
APRIL 2010

**Bristol**  
ENVIRONMENTAL & ENGINEERING  
SERVICES CORPORATION  
Phone (907) 563-0013 Fax (907) 563-6713  
CIVIL

**SHEET INDEX**

**CIVIL**  
COVER SHEET, VICINITY MAP, PROJECT LOCATION MAP, AND SHEET INDEX  
ABBREVIATIONS, LEGEND, AND GENERAL NOTES

C1.0	XX
C1.1	XX
C2.0	XX
C3.0	XX
C3.1	XX
C4.0	XX
C4.1	XX
C5.0	XX

FIGURE 2  
DILLINGHAM, ALASKA  
WASTE WATER TREATMENT PLANT STUDY  
SEWAGE TREATMENT FACILITY IMPROVEMENTS  
COVER SHEET


User: MHIMLER May 06, 2010 - 8:30am  
Drawing: K:\JDBS\210081 VAV TP STUDY\CAD-DESIGN\FEASIBILITY\210081\_FIG\_2.DWG - Layout: LAYOUT1  
Xrefs: None - Images: DILLINGHAM-DRTHD.JPG

User: MHIMLER May 06, 2010 - 8:37am  
 Drawing: K:\DBS\210081 VAVTP STUDY\ACAD-DESIGN\FEASIBILITY\210081\_FIG\_3.DWG - Layout: LAYOUT2  
 Xrefs: BR22X3REV.DWG 20053\_BASE-STL.DWG - Images: (DIESEL evaluation Failed)



**MAPPING NOTES**  
 MAPPING IS BASED ON PHOTOGRAPHY ACQUIRED BY AERO-METRIC INC. ON 7-11-2000 AT A NOMINAL SCALE OF 1"=1000'. MAP PROJECTION IS BASED UPON ALASKA STATE PLANE COORDINATE SYSTEM 1983, ZONE 6.

**1 FACILITY SITE PLAN**  
 SCALE: SHOWN



**PRELIMINARY DESIGN**

REVISIONS				REVISIONS			
NO.	DATE	BY	DESCRIPTION	NO.	DATE	BY	DESCRIPTION

**Bristol**  
 ENVIRONMENTAL & ENGINEERING  
 SERVICES CORPORATION  
 Project No. 210018




DILLINGHAM, ALASKA  
 SEWAGE TREATMENT FACILITY IMPROVEMENTS

**FACILITY SITE PLAN**

SCALE: SHOWN    DESIGNED: FJV    CHECKED: FJV    DRAWN: SJW    DATE: 01/25/10

SHEET NO.  
**FIG 3**  
 SHEET **3** OF 10

**MAPPING NOTES**  
 TOPOGRAPHY IS BASED ON PHOTOGRAPHY ACQUIRED BY AERO-METRIC INC. ON 7-11-2000 AT A NOMINAL SCALE OF 1"=1000'. MAP PROJECTION IS BASED UPON ALASKA STATE PLANE COORDINATE SYSTEM 1983, ZONE 6.



**1 LAGOON PIPING PLAN**  
 SCALE: SHOWN  
 HORIZONTAL SCALE IN FEET



**PRELIMINARY DESIGN**

REVISIONS				REVISIONS			
NO.	DATE	BY	DESCRIPTION	NO.	DATE	BY	DESCRIPTION

**Bristol**  
 ENVIRONMENTAL & ENGINEERING SERVICES CORPORATION  
 Project No. 210018




DILLINGHAM, ALASKA  
 SEWAGE TREATMENT FACILITY IMPROVEMENTS  
**LAGOON PIPING PLAN**  
 SCALE: SHOWN    DESIGNED: FJV    CHECKED: FJV    DRAWN: SJW    DATE: 01/25/10

SHEET NO.  
**FIG 4**  
 SHEET 4 OF 10

User: MHIMLER May 06, 2010 - 8:38am  
 Drawing: K:\JOB\210081\WV\TP STUDY\ACAD-DESIGN\FEASIBILITY\210081\_FIG\_4.DWG - Layout: LAYOUT2  
 Xrefs: BR22X3REV.DWG 20053\_BASE-STL.DWG - Images: (DIESEL evaluation Failed)





- NOTES: 1. SEE DRAWING C-8 FOR YARD PIPING LAYOUT IN LAGOON AREA  
 2. SEE DRAWING C-7 FOR ACCESS ROAD PROFILE AND TYPICAL SECTION.  
 3. SEE DRAWING C-11 FOR DISPOSAL AREA PLAN AND SECTION AND DETAILS OF LAGOON PERIMETER DITCH OUTLET PROTECTION.

**SITE PLAN**  
 1" = 50'

**RECORD DRAWINGS**  
 Revisions Drawn by C. ROBERTS Date 3-23-88

THESE RECORD DRAWINGS HAVE BEEN PREPARED, IN PART, ON THE BASIS OF INFORMATION COMPILED BY OTHERS. THEY ARE NOT INTENDED TO REPRESENT IN DETAIL THE EXACT LOCATION, TYPE OF COMPONENT NOR MANNER OF CONSTRUCTION. THE ENGINEER WILL NOT BE RESPONSIBLE FOR ANY ERRORS OR OMISSIONS WHICH HAVE BEEN INCORPORATED INTO THE RECORD DRAWINGS.

**FIGURE 6**  
**SHEET 6 OF 10**



DSGN	K.B. HEPPE				
DR	C.D. FILER				
CHK	M.A. Schmiege				
APVD					
NO.	DATE	REVISION	BY	APVD	

**REUSE OF DOCUMENTS**  
 THIS DOCUMENT, AND THE IDEAS AND DESIGNS INCORPORATED HEREIN, AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF CH2M HILL AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF CH2M HILL.

**VERTICAL SCALE**  
 BAR IS ONE INCH ON ORIGINAL DRAWING.  
 0  
 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

CITY OF DILLINGHAM  
 DILLINGHAM, ALASKA

SEWERAGE SYSTEM IMPROVEMENTS  
**LAGOON AND ACCESS ROAD SITE PLAN**

SHEET	9
DWG NO.	C-8
DATE	JUNE 1988
PROJ NO.	K20297.A1

Drawing: K:\JOBS\210081 WWTP STUDY\ACAD-DESIGN\FEASIBILITY\210081\_C\_7--8.DWG - Layout: C1.0  
 User: MHILLER May 06, 2010 - 8:48am Xrefs: 20053\_BASE-STL.DWG BR\_11X17L.DWG - Images: DILLINGHAM-ORTHO.JPG DILLINGHAM-ORTHO.JPG LAGOON\_PIPING.TIF




**1 SLUDGE DEWATERING PAD LOCATION**  
 SCALE: NTS

SUMMARY OF QUANTITIES			
ITEM NO.	ITEM	UNIT	TOTAL
-	GEOTEXTILE SEPARATION	SQUARE YARD	7,400
-	EMBANKMENT	CUBIC YARD	9,850
-	IMPERMEABLE LINER	SQUARE YARD	7,400
-	GEO-TUBES	EACH	24
-	6" SECURITY FENCE	LINEAR FEET	1,020
-	COLLECTION SUMP	EACH	1
-	6-INCH SEWER PIPE	LINEAR FEET	330

**MAPPING NOTES**

MAPPING IS BASED ON PHOTOGRAPHY ACQUIRED BY AERO-METRIC INC. ON 7-11-2000 AT A NOMINAL SCALE OF 1"=1000'. MAP PROJECTION IS BASED UPON ALASKA STATE PLANE COORDINATE SYSTEM 1983, ZONE 6.



**2 SLUDGE DEWATERING PAD**  
 SCALE: SHOWN






**PRELIMINARY DESIGN**


**FIGURE 7**  
 DILLINGHAM, ALASKA  
 WASTE WATER TREATMENT PLANT STUDY  
 SLUDGE DEWATERING PAD LAYOUT

<b>Bristol</b> ENVIRONMENTAL & ENGINEERING SERVICES CORPORATION Phone (907) 563-0013 Fax (907) 563-8713 Project No. 210081	<b>DATUM:</b>	<b>DATE</b> APRIL 2010	<b>SHEET</b>
	N/A	DWN. IPP	<b>7</b>
	<b>PROJECTION:</b>	SCALE SHOWN	of
	NONE	APPRVD. TMW	<b>10</b>


Drawing: K:\JOBS\210081\_WWTP\_STUDY\ACAD-DESIGN\FEASIBILITY\210081\_C\_7-8.DWG - Layout: C1.1  
 User: MHILLER May 06, 2010 - 8:49am Xrefs: 20053\_BASE-STL.DWG BR\_11X17L.DWG - Images: DILLINGHAM-ORTHO.JPG DILLINGHAM-ORTHO.JPG LAGOON\_PIPING.TIF



**B EAST-WEST CROSS SECTION**  
SCALE: SHOWN



**C TYPICAL PAD SECTION**  
SCALE: NTS



**D SUMP DETAIL**  
SCALE: NTS


**NOTES**

1. THE CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 3500 PSI AT 28 DAYS.
2. THE IMPERMEABLE LINER SHALL EXTEND FROM THE PAD TO THE INTERIOR OF THE SUMP TO ENSURE NO SEEPAGE OCCURS FROM THE SUMP.
3. THE 4-INCH HDPE SHALL BE GROUTED IN PLACE TO ENSURE A WATER TIGHT SEAL.
4. A GALVANIZED METAL GRATE SHALL BE SECURED TO THE TOP OF THE SUMP. THE GRATE SHALL BE CAPABLE OF SUPPORTING 400 POUNDS AND SHALL HAVE A MAXIMUM THROUGH SPACING OF 3-INCH
5. A 4-FOOT DIAMETER PRECAST STORM DRAIN MANHOLE MAY BE USED IN LIEU OF THE DESIGN SHOWN. THE SEEPAGE AND GRATING REQUIREMENTS SHALL BE MAINTAINED AS INDICATED ABOVE.

**PRELIMINARY DESIGN**

**FIGURE 8**  
DILLINGHAM, ALASKA  
WASTE WATER TREATMENT PLANT STUDY  
SLUDGE DEWATERING PAD DETAILS

<p><b>Bristol</b> ENVIRONMENTAL &amp; ENGINEERING SERVICES CORPORATION Phone (907) 563-0013 Fax (907) 563-6713 Project No. 210081</p>	DATUM:	DATE	SHEET
	N/A	APRIL 2010	8
	PROJECTION:	SCALE	of
	NONE	SHOWN	10
	APPRVD.	TMW	



**PRELIMINARY DESIGN**

**LEGEND**


- DIRECTION OF SURFACE WATER FLOW
- MONITORING WELLS

**FIGURE 9**  
**DILLINGHAM, ALASKA**  
**WASTE WATER TREATMENT PLANT STUDY**  
**PROPOSED SEPTAGE MONOFILL LOCATION**

 <b>Bristol</b> ENVIRONMENTAL & ENGINEERING SERVICES CORPORATION Phone (907) 563-0013 Fax (907) 563-8713 Project No. 210081	<b>DATUM:</b> N/A	<b>DATE:</b> APRIL 2010	<b>SHEET</b>
	<b>PROJECTION:</b> NONE	<b>DWN.:</b> IPP	<b>9</b>
		<b>SCALE:</b> SHOWN	<b>of</b>
		<b>APPRVD.:</b> TMW	<b>10</b>

Drawing: K:\JOBS\210081\_WWTP\_STUDY\ACAD-DESIGN\FEASIBILITY\210081\_FIG\_9-10.DWG - Layout: FIG 4  
 User: MHILLER May 06, 2010 - 8:40am Xrefs: BR\_11X17L.DWG BR\_85X11P.DWG - Images: DILLINGHAM LANDFILL.JPG


**SOURCE:**  
 DRAWING TAKEN FROM HDR ALASKA, INC.  
 HDR CADD FILE: P:\07076.008\ACAD14\CIVIL\DSWC1-4.DWG  
 CITY OF DILLINGHAM SECTION 33 SOLID WASTE FACILITIES TRANSFER STATION  
 & EQUIPMENT BUILDINGS PROJECT. (PROJECT LAYOUT)



**A**  
—  
**SEPTAGE MONOFILL PLAN VIEW**  
SCALE: NTS

NOTES:

1. THE SPACE BETWEEN THE MONOFILL CELLS MAY BE DECREASED AS LONG AS THE SEPTAGE DOES NOT FLOW FROM ONE CELL TO ANOTHER.



**B**  
—  
**SEPTAGE MONOFILL PROFILE VIEW**  
SCALE: NTS

**PRELIMINARY DESIGN**

**FIGURE 10**  
**DILLINGHAM, ALASKA**  
**WASTE WATER TREATMENT PLANT STUDY**  
**PROPOSED SEPTAGE MONOFILL DETAILS**

**Bristol**  
ENVIRONMENTAL & ENGINEERING  
SERVICES CORPORATION  
Phone (907) 563-0013 Fax (907) 563-6713

DATUM: N/A	DATE APRIL 2010	SHEET <b>10</b> of 10
PROJECTION: NONE	DWN. IPP	
	SCALE SHOWN	
	APPRVD. TMW	

**APPENDIX A**

**ADEC Inspection Report (December 2009)**



**DIVISION OF WATER  
WATER QUALITY COMPLIANCE**

555 Cordova Street  
Anchorage, AK 99501  
Phone: (907)269-7560  
Fax: (907)334-2415  
brent.andrews@alaska.gov  
<http://www.dec.state.ak.us/water>

January 5, 2010  
Certified Mail 7008 1830 0003 5208 1895

Mr. Gary Sharrett  
City Of Dillingham  
P.O. Box 889  
Dillingham, AK 99576

**SUBJECT:** Recent inspection of Dillingham Wastewater Treatment Facility

Dear Mr. Sharrett:

On December 7, 2009 the Alaska Department of Environmental Conservation conducted an inspection of Dillingham WWTF for which we greatly appreciated the facility's cooperation and assistance. Please review the enclosed inspection report and if you have any questions or comments feel free to contact me.

Thank you and sincerely,



Brent Andrews  
Water Quality Compliance Program

Enclosure: APDES Inspection Report

		<b>APDES INSPECTION REPORT</b>			ADEC APDES Inspection Form Last Updated (4/08)									
		Alaska Department of Environmental Conservation Division of Water 555 Cordova St. – Anchorage, AK 99501			Phone: (907)269-7560 Fax: (907)334-2415									
Section 1: General Data														
Inspection Date	Permit Number	Facility Type	Receiving Waters	Weather	Borough									
December 7, 2009	AKG570018	Wastewater Treatment/ Category 3	Nushagak River	Conditions: Partly ~ 35° F Last Rainfall: Unknown	Bristol Bay Borough									
<b>ANNOUNCED</b>			<b>SURFACE WATER</b>											
Section 2: Facility Data														
Name of Site/Facility		Location		Entry Time:	Permit Effective:									
Dillingham Sewage Treatment Facility		Lat: N 59°02'19"		11:00 AM	7/21/2004									
		Long: W 158°27'06"		Exit Time: 3:15 PM	Permit Expiration: Administratively Extended									
Address			Inspection Participants											
City Of Dillingham P.O. Box 889 Dillingham, AK 99576			Brent Andrews / ADEC Gary Sharrett / City Of Dillingham											
On-Site Representative			<table border="0"> <tr> <td>Yes:</td> <td>No:</td> </tr> <tr> <td>Samples Taken: <input checked="" type="checkbox"/></td> <td></td> </tr> <tr> <td>Photos Taken: <input checked="" type="checkbox"/></td> <td></td> </tr> <tr> <td>Analytical Results:</td> <td style="text-align: center;"><input checked="" type="checkbox"/></td> </tr> </table>				Yes:	No:	Samples Taken: <input checked="" type="checkbox"/>		Photos Taken: <input checked="" type="checkbox"/>		Analytical Results:	<input checked="" type="checkbox"/>
Yes:	No:													
Samples Taken: <input checked="" type="checkbox"/>														
Photos Taken: <input checked="" type="checkbox"/>														
Analytical Results:	<input checked="" type="checkbox"/>													
Responsible Official(s)														
Gary Sharrett / Janice Shilanski														
CONTACTED PHONE														
(907)842-5048														
Section 3: Findings														
Background														
<p>The Dillingham Sewage Treatment Facility (Wastewater Treatment Plant / WWTF) was built in July of 1988 as a two-cell aerated lagoon system. According to Mr. Sharrett, the plant operator, there haven't been any major improvements or upgrades since then. The City Of Dillingham's public works department manages the plant and employs Mr. Sharrett full-time with one assistant who are both on-call around the clock. The facility serves a population of 2800, while some in Dillingham are on a septic system that is pumped to trucks and then into the main lagoon. The facility has an authorized continuous discharge of .273 million gallons a day (mgd) into the Nushagak River – one of the most important fishing resources in the state.</p>														

Dillingham WWTF

Inspection Report

12/7/2009

**Regulatory Status/Compliance History**

While there are no current enforcement actions against the City of Dillingham, previously a Compliance Order By Consent (COBC) was drafted by the Department (the Alaska Department of Environmental Conservation / ADEC / DEC) due to numerous and ongoing water quality violations; however, this pending COBC is now dependent on the inspection described here. Municipal Grants and Loans in this Department has also recently focused on improving drinking water and wastewater systems in Dillingham.

Previous to the inspection, Mr. Sharrett and I had been in contact several times about non-compliant discharge monitoring reports (DMR's) that included violations of the fecal coliform count, as well as several violations of the required percentage removal of total suspended solids (TSS), and biochemical oxygen demand (BOD<sub>5</sub>). The field inspection conducted on December 7<sup>th</sup>, 2009 would point to many of these same problems.

**Field Inspection**

Mr. Sharrett escorted me to the City's Public Works Department (Appendix A) on December 7<sup>th</sup>, where we arrived at 11:00 AM. An interview was conducted, followed by a facility tour, and a detailed review of 2009's DMRs. The inspection took about four and a half hours.

First, initial basic questions were asked about the above background and compliance history. After this, permit, management questions, and treatment system questions were asked. With regard to the permit, the facility did not have a printed copy of it on hand. They did however, have a copy of the authorization. And the Department also received a new notice of intent (NOI) to discharge from Dillingham on March 17, 2009. This NOI was for extended coverage under a new permit, should one be issued, especially since the permit that Dillingham is currently operating under expired July 20, 2009. DEC has granted continued administrative coverage though. At the same time, the facility should have a letter stating this, but DEC never issued such a letter. If, or as soon as one is issued, it ought to be kept on-site with the permit, the authorization, and/or the original acknowledgement of coverage.

Mr. Sharrett is listed as the operator and on-site contact on the NOI. He has been with the City and in his current role for 13 months. The NOI lists, "[no significant changes] to the quantity or quality of wastewater discharged;" however, Mr. Sharrett expressed concern to me over fecal coliform violations, the age of the system, contributions from septic vendors, sludge removal, infiltration into the lift stations, and infiltration of sewage and wastewater into soils surrounding the lift stations. The treatment system includes seven lifts, all with locks and alarms (Appendix E). The main "dock" lift station has a grinder pump in it that transports waste to the lagoon where one cell is being used as a polishing pond. The City also maintains two other grinder pumps in the system. Wastewater, once treated, is continually discharged through 1700 feet of 12 inch pipe. The outfall terminates into the Nushagak River at a depth of -9 ft. MLLW (mean low low water) where a mixing zone has been authorized.

While it may be easier to comply with water quality standards (WQS) enforced at the edge of the

## Dillingham WWTF

## Inspection Report

12/7/2009

mixing zone, those of 18 AAC 70, these standards do not supersede those of 40 CFR 133 – so both regulations must be met.<sup>1</sup> Alaska water quality standards are actually slightly more stringent than the federal standards; Alaska thus often authorizes a mixing zone (based on use analysis) whose size is either calculated by a dilution factor or a flow model. Effluent which is compliant with the federal standards is then supposedly “automatically” compliant with Alaska WQS at the edge of the mixing zone.<sup>2</sup> While greater dilution in the mixing zone is not only possible but often occurs, ADEC still requires facilities to sample along the mixing zone to ensure their compliance. After discussing it with Mr. Sharrett, I discovered that the facility was not doing the required mixing zone sampling. Next, Part II.D. of the Permit specifies that the facility must have a Quality Assurance Project Plan (QAP) in place to make certain that data is properly collected and analyzed, valid and verifiable. Dillingham WWTF did not have a QAP in place during the inspection. At the same time however, the facility takes a variety of grab and composite samples that they will want to confirm are collected according to a plan. If the facility would like, the State provides a generic plan that can be used; details are in the permit. Dillingham WWTF also has some specific practices that they may want to write into their own QAP. For instance, I noted that 24-hour composite samples are usually collected at 9 AM, 5 PM, 1 AM, and again at 9AM so that they make the morning Alaska Airlines/PenAir flight out of Dillingham and are thus within required holding times when they get to Analytica, a DEC certified laboratory. The chain-of-custody procedures will also want to go in the QAP.

Holding times for fecal coliform counts should be 6 hours according to 40 CFR 136.3 but must be less than 36. Mr. Sharrett reports that often sample analysis extends into the 36 hour window and that he had to resample once when the couriers took too long. He also stated that after working with Analytica for a while, holding times are getting better. In addition to checking for the QAP, I looked to make sure *Standard Methods* were being used. The facility should have a copy of this text on hand. An MSDS book is also a good idea, and several MSDS sheets were observed during the inspection walk-around (Picture 19). An operations and maintenance (O&M) manual was also found. Mr. Sharrett performs routine maintenance and fixes anything in the system that needs specialized knowledge. The City's crew, together with Mr. Sharrett, perform good housekeeping, clean-up, and janitorial measures throughout the system. If the City was to have a power outage, blowers would have to be reset, and lift stations would have to be checked, especially the dock lift. While there are alarms on the lift stations for high levels, if levels get too high, the City can also contract a pumper to help.

After leaving the Public Works building, Mr. Sharrett and I went to look at the lagoon and outfall. Upon approaching the facility, it was evident that there was fence up and a lockable gate (Picture 1). However, the sign at the entrance merely said “No Trespassing” and did not identify the plant as the City Of Dillingham Sewage Treatment Facility. Snow piled up high next to the gate also made some fence appear if it was falling down (Picture 2). We drove past the blower room and lab (Picture 3) and to the side of the lagoon (Picture 4). This is where one of the sewage inlets can be seen (as in Picture 5 and Appendix D). Also immediately to the right, a ditch containing stormwater was observed (Picture 6). This ditch, according to Mr. Sharrett, is not connected to or part of the treatment system. At the same time, due to the ditches close proximity to wastewater (Picture 7) and the fact that the lagoon is not lined, potentially serious water quality impairments may be

<sup>1</sup> See 18 AAC 70.020(b), and 40 CFR 133.102/40 CFR 133.105 specifically.

<sup>2</sup> And vice versa. If you're non-compliant with the effluent treatment requirements you're theoretically non-compliant with the mixing zone WQS authorized limits.

## Dillingham WWTF

## Inspection Report

12/7/2009

present in the ditch via runoff or percolation. Testing stormwater in the ditch would be the only way to know. Nearby, less than 25 feet from the ditch, raw sewage from a septic vendor had been recently dumped (Picture 8). Dumped sewage is intended to be treated in the lagoon; however, it was noticed that the most direct distance to Cell 2, along the side of the lagoon, was not aerated (Picture 9). After this, Mr. Sharrett opened the inlet diversion box, where influent flows from. I estimated that influent entering the lagoon normally must pass through about 200 feet of aeration, whereas pumped sewage receives only about 100 feet of primary treatment passing alongside the basin. We also briefly observed the overflow control manholes, aka Cell 1's bypass system.

Next, we entered the blower building. Blower motors appeared well maintained and in good condition (Picture 12). In the blower room some safety equipment was noticed (Picture 13), a first aid kit as well, and a lab area. Near the lab area, Mr. Sharrett's Wastewater Treatment 2 certificate from the State of Alaska was photographed (Picture 14). Passing through fairly quickly, and just outside again, the "HUD" lift was looked at. Mr. Sharrett discussed the possibility of using this lift as an alternate dumping area for the pump truck.<sup>3</sup> If this is a viable option, the capacity of the station would have to be carefully assessed. Mr. Sharrett also talked about doing some pretreatment nearby with the use of an 8000 gallon storage tank, grit chamber, and pre-aeration.

At the effluent Mr. Sharrett took a grab sample (Pictures 15/16) which then D.O. and pH were measured off of (Picture 17). pH measured 7.5 and the measurement was not duplicated. The D.O. meter was not calibrated before, but the membrane was O.K., and the sample was actively stirred. A stable reading of 5.4 mg/l was found. Despite that this is above the permit authorization minimum of 2.0 mg/l for D.O., the Alaska Water Quality Standard specifies that, "D.O. must be greater than 7 mg/l in waters used by anadromous fish... In no case may D.O. be greater than 17 mg/l." Because of the Nushagak's status as a fish bearing water body, a D.O. reading of 5.4 mg/l may be a potential violation of WQS's. When I next asked how the facility measured flow, Mr. Sharrett stated that a letter from DEC allowed them to report a daily quantity of .273 million gallons, and that the facility did not actually monitor or know how flow fluxuated. Unfortunately this number is used in some effluent calculations such as pounds per day removed, and by using such an assumed flow rate the facility could be overestimating some of the numbers it reports. I discussed this possibility briefly with Mr. Sharrett.

As we were leaving the facility to view the outfall I jotted some additional notes on the lagoons. First, it looked like there was plenty of freeboard; the lagoon averages 14 ft. deep, and freeboard was 4 ft., so therefore it might hold 1/3<sup>rd</sup> more. Also, there was no erosion or seepage evident, and no floating material; there were however a few dead spots near the edges and some grass and vegetation even though Mr. Sharrett stated that a backhoe had dug most of it up in the summer. We also talked about the need to dredge sludge since it has never been done. This is probably pressing.<sup>4</sup>

We found the outfall more than 1/4 mile away. I hiked down a hillside and found a sign pointed toward an icy access road (Picture 20/21). Ice was also flowing in the Nushagak River at a fairly decent speed, probably helping to disperse pollutants at that point in the tide. No foams, grease, sheen, colors, or other wastewater remnants were observed.

<sup>3</sup> Because the lift pumps to the inlet in Picture 5.

<sup>4</sup> See 40 CFR 503 for specific regulations regarding sludge removal.

Dillingham WWTF

Inspection Report

12/7/2009

<p>To conclude the inspection, evaluation of 2009's DMRs was conducted by hand. My tally illuminates some problems with effluent sampling and treatment effectiveness. 4 D.O. violations were found, 4 fecal coliform mixing zone violations, 1 BOD<sub>5</sub> concentration and 3 BOD<sub>5</sub> percent removal and 3 TSS percent removal violations were discovered; moreover, the facility reported 20 violations for 20 sampling results for fecal coliform concentrations – all in 2009. There were no violations for pH or TSS concentrations.</p>
<p><b>Sampling Activities</b></p>
<p>While DEC did not sample, the facility did and the sample results are described above.</p>
<p><b>Records Review</b></p>
<p>All records reported here were reviewed on-site.</p>
<p><b>Summary</b></p>
<p>In 2009 the facility recognized that ongoing problems were present. Effluent limitations were not being met, especially for fecal coliform counts, but also for removal of TSS and BOD<sub>5</sub>. Possibly adding to these problems, the facility's choice not to monitor flow could skew pounds per day removed as it's calculated on DMR's. Mixing zone sampling was also not conducted in 2009. Other problems like sludge removal, the lagoon not being lined, and possible infiltration from the lifts to stormwater flows and soils also plague the City.</p> <p>Paperwork items are of some concern too. First, the required copy of the permit was not on-hand. Next, the facility was missing a OAP, required by section II.D of the permit.</p>
<p><b>Section 4. Compliance Recommendations</b></p>
<p><b>Administrative Violations</b></p>
<p>35 violations were found during the inspection. Once again those were:</p> <ul style="list-style-type: none"> <li>• 20 fecal coliform concentration violations,</li> <li>• 6 percent removal violations,</li> <li>• 4 mixing zone violations,</li> <li>• 4 D.O. concentration violations, and</li> <li>• 1 BOD<sub>5</sub> concentration violation.</li> </ul>
<p><b>Potential Water Quality Violations</b></p>
<p>D.O. above the minimum permit authorized limit but below the minimum limit allowed for the growth and propagation of aquatic life may be an additional violation; also several pH measurements on Dillingham's DMRs were above 8.5, which is pH's limit for anadromous waterbodies; however, the City again has an authorized permit limit of 9.0 and no readings were recorded this high in 2009. Mixing zone sampling will be needed to verify and determine the extent of the D.O. and pH problems described here, if any exist. Also, while the permit specifies that "a copy of [the] general permit must be kept at the site where discharges occur," and there wasn't one on site, the permit can easily be obtained from the internet. Still, having a printed copy is</p>

Dillingham WWTF

Inspection Report

12/7/2009

sometimes necessary, and not having one is a potential violation. The same is true for the QAP, it can be easily obtained online, but the facility should have one immediately available. Additionally, any correspondence that backs up the facilities authorization to discharge needs to be kept with the permit. The facility should also have a copy of *Standard Methods* on hand. Lastly, signage for the entrance of the treatment works should properly identify the facility.

Action Items


- To alleviate ongoing or potential water quality violations the following recommendations are made:
1. Collect the permit, authorization, and any similar correspondence in a location that can be accessed at a moment's notice.
  2. Generate a QAP that describes sampling procedures in line with *Standard Methods* and has facility specific practices described as well. Include with the QAP, the normal chain-of-custody procedure and the normal DEC certified laboratory used for sample analysis.
    - a. Keep chain-of-custody records in a file as specified by Section III.F of the Permit.
  3. With DMR's keep non-compliance reports.<sup>5</sup>
  4. Keep MSDS and O&M books both in the lab and in the public works building (see Sections IV.H and IV.E for more).
  5. Within 30 days, develop a plan to reduce the chronic nature of ongoing water quality violations. This may include moving the septic dumping site, aerating dead spots, installing curtains, removing sludge, adding disinfection, or any other measures the City sees fit. It is up to the City to determine what is needed, but remember that ongoing violations have potentially serious implications, including monetary and criminal penalties. If desired an engineer's assistance is available through the Alaska Native Tribal Health Consortium (ANTHC) and DEC can put you in touch with that engineer if you require their contact information.
  6. Please also include within the plan, future mixing zone sampling activities.
    - a. Plan on sampling the edge of the mixing zone for D.O. and pH as well.
  7. Hang a sign identifying the lagoon as a treatment works, although keep the trespassing notices up as well.
  8. Sample the stormwater ditch next to the lagoon for fecals and other pollutants. You may want to sample in the ditch and at the ditches outfall.

Please remember that these are only recommendations; they do not bear the force of formal enforcement action.

Signatures

Thank You

Thank you for having me at your facility.

 Inspector	Date: January 6, 2010
Date:	
Brent J. Andrews - Environmental Program Specialist II	

<sup>5</sup> See III.G of the Permit... although it's not specific to records retention.

Dillingham WWTF

Inspection Report


12/7/2009

<p>Alaska Dept. of Environmental Conservation Division of Water – Compliance Program 555 Cordova St. – Anchorage, AK 99501 P: (907)269-7560 C: (907)723-6822 brent.andrews@alaska.gov</p>	
---	--

Dillingham Wastewater Treatment Facility

Inspection Report



December 7, 2009

Photo Addendum		
Photo 001	Photo 002	Photo 003
		
Gate (Facility Unidentified)	Additional Fencing (Some Below Snow Height)	Blower Room / Lab
Photo 004	Photo 005	Photo 006
		
Aeration / (Inflow Next to Truck)	(Inflow Next to Truck in Picture 4)	Ditch (Next To Lagoon)

Dillingham Wastewater Treatment Facility

Inspection Report






December 7, 2009

Photo Addendum		
Photo 007	Photo 008	Photo 009
		
Ditch Proximity to Treatment Facility	Recently Dumped Sewage	Proximity of Septic Dump to Lagoon Outfall
Photo 010	Photo 011	Photo 012
		
Facility Panorama	Polishing / Sedimentation Lagoon	Blowers

Dillingham Wastewater Treatment Facility

Inspection Report



December 7, 2009

Photo Addendum		
<p>Photo 013</p>  <p>Safety Equipment (in Blower Room)</p>	<p>Photo 014</p>  <p>Mr. Sharrett's WT2</p>	<p>Photo 015</p>  <p>Effluent / Sampling Point</p>
<p>Photo 016</p>  <p>Sample Taken</p>	<p>Photo 017</p>  <p>Testing for pH and D.O.</p>	<p>Photo 018</p>  <p>pH Calibration (7.0 Buffer Expiration Unknown)</p>

Dillingham Wastewater Treatment Facility

Inspection Report

December 7, 2009

Photo Appendix		
Photo 019	Photo 020	Photo 021
		
Some MSDS Sheets	Outfall Sign (GPS Coordinates Section 2)	Outfall / Nushagak River

Dillingham WWTF

Inspection Report

12/7/2009

**Appendix**

**Appendix A: Public Works Building**




**Appendix B: Aerial Photo**





Appendix C: Topographic Map of Area




Appendix D: Facility Diagram





Appendix E: Lift Stations Locations



## **APPENDIX B**

### **Preliminary Engineers Estimates**



PRELIMINARY ENGINEER'S ESTIMATE

Sludge Dewatering Pad

Item	Estimated Quantity	Unit of Measure	Unit Bid Price	Total
Mobilization/Demobilization	1	Lump Sum	\$ 5,000.00	\$ 5,000.00
Construction Surveying	1	Lump Sum	\$ 5,000.00	\$ 5,000.00
Embankment	9850	Cubic Yard	\$ 30.00	\$ 295,500.00
Impermeable Liner	7400	Square Yard	\$ 4.00	\$ 29,600.00
Geotextile	7400	Square Yard	\$ 2.00	\$ 14,800.00
Culvert (18")	20	Linear Foot	\$ 95.00	\$ 1,900.00
Sump	1	Each	\$ 5,000.00	\$ 5,000.00
6" HDPE Pipe	330	Linear Foot	\$ 50.00	\$ 16,500.00
Fence	1020	Linear Foot	\$ 100.00	\$ 102,000.00

Subtotal \$ 475,300.00

Contingency 15% \$ 71,300.00

**Total Construction Costs \$ 550,000.00**

Assumptions:

1. Local contractor will perform the construction.
2. Geotubes and associated pumps for filling are not included.

PRELIMINARY ENGINEER'S ESTIMATE  
Septage Disposal Station @ WWTP

Item	Estimated Quantity	Unit of Measure	Unit Bid Price	Total
Mobilization/Demobilization	1	Lump Sum	\$ 15,000.00	\$ 15,000.00
Site Preparation	1	Lump Sum	\$ 10,000.00	\$ 10,000.00
Site Electrical	1	Lump Sum	\$ 22,000.00	\$ 22,000.00
Collection System	1	Lump Sum	\$ 12,000.00	\$ 12,000.00
5000 gal Tank	1	Lump Sum	\$ 35,000.00	\$ 35,000.00
Macerator Pump system	1	Lump Sum	\$ 18,000.00	\$ 18,000.00
Discharge Piping	350	Linear Foot	\$ 200.00	\$ 70,000.00

	Subtotal		\$ 182,000.00
	Contingency	15%	\$ 27,300.00
<b>Total Construction Costs</b>			<b>\$ 210,000.00</b>

Assumptions:

1. Local contractor will perform the construction.
2. Disposal Site will Utilize a portion of the Sludge dewatering pad.
3. Assumes year round use.
4. Allow for \$20,000 annual O&M.

PRELIMINARY ENGINEER'S ESTIMATE  
Septage Monofill

Item	Estimated Quantity	Unit of Measure	Unit Bid Price	Total
Mobilization/Demobilization	1	Lump Sum	\$ 5,000.00	\$ 5,000.00
Construction Surveying	1	Lump Sum	\$ 10,000.00	\$ 10,000.00
Clearing and Grubbing	2.5	Acre	\$ 10,000.00	\$ 25,000.00
Embankment (Road)	2500	Cubic Yard	\$ 30.00	\$ 75,000.00
Geotextile (Road)	3800	Square Yard	\$ 2.00	\$ 7,600.00
Excavation	1600	Cubic Yard	\$ 7.50	\$ 12,000.00
Cover Ditch w/ Excavation	500	Cubic Yard	\$ 7.50	\$ 3,750.00
Fence	1800	Linear Foot	\$ 100.00	\$ 180,000.00

Subtotal		\$ 318,350.00
Contingency	15%	\$ 47,760.00

**Total Construction Costs                   \$ 370,000.00**

Assumptions:

1. Local contractor will perform the construction.
2. The construction costs indicated reflect the first year start-up cost.
3. The anticipated annual cost for excavating and covering the monofill is \$18,000.
4. Construction costs would be eligible under existing ADEC solid waste grant.



**APPENDIX C**

**USACE Memorandum of Snag Point Bank Stabilization Inspection**



CEPOA-EN-CW-HH (1105-2-10b)

MEMORANDUM THRU CEPOA-EN-CW-HH (Eisses), FOR THE RECORD

SUBJECT: Inspection of Completed Works, Dillingham Bank Stabilization, Snag Point Bulkhead, Dillingham, Alaska 21 September 2009.

1. GENERAL: On September 21, 2009 Mary Azelton (CEPOA-EN-CW-HH) and Robert Tedrick (CEPOA-EN-CW-HH) traveled to Dillingham, Alaska. The purpose of this visit was to inspect the erosion protection project placed by the Corps of Engineers on the shoreline at Dillingham, Alaska in 1999. The location of the bulkhead is directly adjacent to the city dock.
2. BACKGROUND: Dillingham is located at the extreme northern end of Nushagak Bay in northern Bristol Bay, at the confluence of the Wood and Nushagak Rivers. It is approximately 327 miles southwest of Anchorage and is a 6 hour flight from Seattle. Dillingham is located in the Bristol Bay recording district.
3. OBSERVATIONS:
  - a. We began the inspection at 1030 and finished at approximately 1230. The weather during the inspection was lightly overcast with a few light rain showers, and clearing as the morning progressed. The temperature was approximately 50°F.
  - b. The tide was going out during the inspection with the low tide occurring at 1300 and the high tide at approximately 1915 that day. The tide at Dillingham can see fluctuations in the 20 foot range.
  - c. We inspected the revetment from west to east following the toe of the bulkhead and then walked from east to west along the top of the bulkhead. The project appears to be in overall good condition with no visual signs of distress.
  - d. This inspection is a follow up to a September 25, 2008 inspection that we conducted to evaluate scour at the bulkhead toe.
  - e. Scour measurements were taken from mud-line to top of lower wale channel using a fiberglass rod. The rod was held vertically at the base of the wall, resting on the mud-line. Readings were taken by eye from near the river's edge. Design Wale elevation taken from design drawings was 22.5' with a 2.5" spacing between wale channels. Design survey mud-line elevations (see Figure 1.) have been estimated from the contract drawing site plan.
  - f. Scour at toe in some locations exceeds design scour allowance, see Figure 1.
  - g. Our comparison of the design drawings and the as-built information revealed a conflict in the design drawings that was apparently not resolved in a conservative manner. Tie rod spacing is typically 16' with 12'-6" spacing used in areas where the original mud-line elevation was below 17' MLLW. Site plan drawing C-2 shows the smaller spacing from STA 20+60 to STA 23+30. Typical Section A on drawing C-3 indicates the tighter spacing to be from STA 20+60 to STA 22+30. The as-built drawings for the project indicate that the layout indicated on drawing C-3 was followed. Thus, approximately 100' of the bulkhead was built with 16' tie rod spacing where 12'-6" spacing was intended by the designer.
  - h. Access ladders were noted at the following stations: 13+26, 15+79, 16+81, 19+68 and 23+00. Ladders are extensively damaged (possibly from ice) and are non-functional.

- i. Exposed force main was visible at station 21+00 for approximately 19' and then again at station 22+50 for 63'. This line is identified as a 10" ductile iron force main on the project drawings.
  - j. Approximately 37' of sewer pipe (HDPE with concrete anchor blocks) was exposed near the east end of the bulkhead. This line is identified as a 12" sewer outfall on the project drawings. The anchor blocks are visible a photo taken during the 2008 inspection.
  - k. At station 23+93 there is a slight bulge in the waler. This was not noticed on the previous year's inspection and will be monitored on future inspections.
  - l. Drainage at bulkhead appears to be functioning well.
  - m. See Figure 1. for a table of scour measurements.
  - n. Photographs from inspection follow.
4. Recommendations:
- a. Continue annual monitoring of scour at the base of the bulkhead.
  - b. Ladders need to be repaired, extended to near the mud-line, and maintained.
  - c. Provide protective cover for the 10" ductile iron force main to prevent this line from damage that could cause an uncontrolled discharge of sewage. The cover for this line should be monitored, especially after storms.
  - d. Monitor the exposure of the sewage outfall, especially after storms.
  - e. Annually monitor the small bulge noted in the waler near STA 23+93.
5. For additional information please contact Mary Azelton (phone 907-753-5706, email [Mary.T.Azelton@usace.army.mil](mailto:Mary.T.Azelton@usace.army.mil)) or Robert Tedrick (phone 907-753-5745, email [Robert.C.Tedrick@usace.army.mil](mailto:Robert.C.Tedrick@usace.army.mil)).

 2/18/2010  
MARY AZELTON  
Hydraulic Engineer  
Hydraulics/Hydrology Section

 2/18/10  
ROBERT TEDRICK, P.E.  
Structural Engineer  
Hydraulics/Hydrology Section

Enclosure: 1 Figure  
13 Photos

STATION	DESCRIPTION	Approximate Design Survey Toe Elevation (ft)	Minimum Design Toe Elevation with 5' Scour (ft)	Approximate Measured Toe Elevation Sept 25 2008 (ft)	Approximate Measured Toe Elevation Sept 21 2009 (ft)	CHANGE (2009 minus 2008) Positive is increased scour (ft)
10+00	Begin Bulkhead	25	12	N/A	N/A	
10+90	Angle Point 1	18.5	12	18.3	17.7	0.6
11+00		18.5	12	17.8	17.5	0.3
12+00		18.5	12	16.6	15.8	0.9
13+00		18.5	12	15.7	15.7	0.0
13+10	Angle Point 2	18.5	12	15.7	15.5	0.2
14+00		18.25	12	15.0	14.1	0.9
15+00		17	12	14.1	13.8	0.3
15+30	Angle Point 3	17	12	13.9	14.0	0.0
15+85 -	End Low Wall	17.25	12	13.1	12.9	0.2
15+85 +	Begin High wall	17.25	10	13.0	13.0	0.0
16+00		16.5	10	12.6	12.8	-0.1
16+40	Angle Point 4	14.5	10	11.3	11.4	-0.1
17+00		16.5	10	13.2	12.7	0.5
17+20 -	End High Wall	17	10	13.7	12.8	0.9
17+20 +	Begin Low Wall	17	12	13.6	12.9	0.7
18+00		18	12	13.9	13.4	0.5
19+00		18.25	12	13.2	12.5	0.7
19+04	Storm Drain Conn	17.5	12	13.2	12.7	0.5
19+68	Angle Point 5	20	12	13.2	12.2	1.0
20+00		19	12	11.8	11.3	0.5
20+75 -	End Low Wall	16.5	12	9.5	9.6	-0.1
20+75 +	Begin High wall	16.5	10	9.4	9.6	-0.2
21+00		15.5	10	8.6	8.7	-0.1
21+10	Angle Point 6	15	10	9.2	8.5	0.7
22+00		15.75	10	9.8	10.2	-0.4
22+50	Angle Point 7	15.5	12	9.6	9.1	0.5
22+80 -	End high wall	17	12	10.6	9.4	1.2
22+80 +	Begin Low Wall	17	12	10.7	9.5	1.3
23+00		17.75	12	11.0	10.3	0.7
24+00		17	12	12.0	11.7	0.3
25+00		17.75	12	12.1	11.7	0.4
25+39	Angle Point 8	17.5	12	12.2	11.7	0.6
25+58	@ flat rock	N/A	12	N/A	N/A	N/A
26+00		22	12	N/A	N/A	N/A
26+02	Angle Point 9	22	12	N/A	N/A	N/A
26+25	End Bulkhead	30	12	N/A	N/A	N/A
Red toe elevations are below the minimum design scour elevation.						
Light gray shading indicates areas built for scour to +10' MLLW						
Darker gray shading indicates area were there was a conflict in anchor rod spacing on the design drawings. Anchor rod spacing in this area is @ 16', should have been 12'-6".						

Figure 1. Measurements taken from 2008 and 2009 inspections



Photo 1 Beginning of sheet pile bulkhead – Angle Pt. #1 @ STA 10+90



Photo 2 Damaged access ladder near angle Pt. #5 @ STA 19+68



Photo 3 Sheet pile bulkhead – Small bulge in wale @ tie rod @ STA 23+93



Photo 4 End of sheet pile bulkhead – Angle Pt. #8 @ STA 25+39



Photo 5 Exposed section of HDPE sewage outfall pipe



Photo 6 Exposed section of sewage outfall – Approx. 37' between outermost blocks



Photo 7 Erosion adjacent to project @ upstream/up-station end



Photo 8 Top of wall looking down station



Photo 9 Top of wall looking up station



Photo 10 Exposed force main parallel to bulkhead – Approx. 63' near STA 22+50



Photo 11 Top of bulkhead looking down station



Photo 12 Drainage near weep hole at top of bulkhead



Photo 13 Top of bulkhead looking down station

CITY OF DILLINGHAM, ALASKA

RESOLUTION NO. 2010-89

**A RESOLUTION OF THE DILLINGHAM CITY COUNCIL APPROVING THE FY2012 CAPITAL IMPROVEMENT PROJECTS PLAN**

WHEREAS, Dillingham Municipal Code 2.68.160 requires that the Dillingham Planning Commission prepare and recommend to the City Council an annual update of a Capital Improvement Plan; and,

WHEREAS, staff and the public prepared proposals from August 3 to September 13, 2010; and,

WHEREAS, the Planning Department reviewed 41 nominations from staff and the public; and,

WHEREAS, a Project Review Committee, comprising of the Finance Director, the City Manager, the Public Works Director, and the Planning Director reviewed the projects at public workshops September 14 and 16; and,

WHEREAS, the PRC ranked the projects for feasibility, compliance issues, and other pertinent criteria September 20th; and,

WHEREAS, the Planning Commission held public hearings on September 21 and October 5; and,

WHEREAS, the Planning Commission ranked each of the projects based on the community values of impact on community quality of life, health and safety, sustainability, and economic development; and,

WHEREAS, on October 5<sup>th</sup> the Planning Commission passed Resolution 2010-09, recommending a FY2012 Capital Projects list to the City Council; and,


NOW, THEREFORE, BE IT RESOLVED that the Dillingham City Council approve and adopt the attached FY2012 Capital Improvement Projects Plan.

PASSED and ADOPTED by the Dillingham City Council on October 19, 2010.

SEAL:

  
Alice Ruby, Mayor

ATTEST:

  
Janice Shilanski, City Clerk

City of Dillingham Information Memorandum No. R2010-89


Subject: A Resolution of the Dillingham City Council supporting adoption of the FY2012 Capital Improvements Projects Plan

Agenda of: October 19, 2010

City Council Action:

Manager: Recommend approval.

City Manager:



Donald Moore

Route To:	Department / Individual	Initials	Remarks
	Finance Director		
X	Planning Director		
X	City Clerk		

Attachment (s). Capital Improvement Projects Plan.

Fiscal Note: Yes \_\_\_ No X Funds Available: Federal and state funding request


Summary Statement.


The FY2012 Capital Improvement Projects List was submitted by the Dillingham Planning Commission. This Resolution supports adoption of the FY2012 CIP Plan.

## FY12 Capital Improvement Projects List

1. Wastewater Treatment Plant Upgrades
2. Emergency Bank Stabilization at Harbor
3. Snag Point Sewer Line and Force Main
4. Lift Stations
5. Water System Improvements
6. Water Loop Downtown
7. Update 2003 Water and Sewer Master Plan
8. Downtown Streets Rehabilitation
9. D Street Road Repair and Pedestrian Path
10. Fire Station and Public Safety Building Planning
11. Tanker Truck
12. Equipment Replacement – Public Works, Public Safety
13. Erosion - Squaw Creek to Kananak Beach
14. Kananak Road and Multi-Use Path
15. Library Roof
16. Senior Center Renovation
17. Harbor East and South Bulkhead
18. Dry Hydrant Reservoir System
19. Fire Control for Landfill
20. Nerka Roads
21. Swimming Pool
22. Landfill Incinerator
23. Greenhouse
24. Hockey Rink Roof
25. Ball Field/Park
26. City Cemetery
27. Live Fire Training Structure
28. Skateboard Park
29. H Harvey Samuelson Community Cultural Center
30. Lupine Culvert
31. Storage Building
32. Custom Fish Processing Plant

PASSED and ADOPTED this 19<sup>th</sup> day of October, 2010.

  
\_\_\_\_\_  
Alice Ruby, Mayor

  
\_\_\_\_\_  
Janice Shilanski, City Clerk

CITY OF DILLINGHAM, ALASKA

RESOLUTION NO. 2010-56

**A RESOLUTION OF THE DILLINGHAM CITY COUNCIL DESIGNATING STATE OF ALASKA DEPARTMENT OF ENVIRONMENTAL CONSERVATION (AKDEC) GRANT FUNDS FOR THE PROJECT ENTITLED WASTEWATER TREATMENT PLANT IMPROVEMENTS PHASE 1 AS THE NUMBER ONE LOCAL STATE FUNDING PRIORITY FOR FISCAL YEAR 2012.**

---

WHEREAS, the City of Dillingham, through the State of Alaska, Department of Environmental Conservation, will request grant funding for the Wastewater Treatment Plant Improvements Phase 1; and,

WHEREAS, the State of Alaska, Department of Environmental Conservation has requested that the City of Dillingham identify if this project is the community's number one local state funding priority for fiscal year 2012; and,

WHEREAS, water and sewer system improvements were identified as a health and safety priority in the 2003 Dillingham Water and Sewer Master Plan, prepared by Bristol Environmental and Engineering Services Corporation ("BEESC"); and,

WHEREAS, the sewage lagoon is in urgent need of desludging due to lack of sludge removal since it was installed over 22 years ago; and,


WHEREAS, improvements must be made to the Wastewater Treatment Plant and the landfill before sludge removal can occur; and,

WHEREAS, Phase I of the Wastewater Treatment Plant Improvements will design, permit, and construct a sludge disposal station, sludge dewatering pad, and begin removing sludge from the sewage lagoon;

NOW, THEREFORE, BE IT RESOLVED that the Dillingham City Council designates the Wastewater Treatment Plant Phase I Improvements as the number one local state funding priority for fiscal year 2012.

APPROVED AND ADOPTED this 5th day of August, 2010.

SEAL:

  
Alice Ruby, Mayor

ATTEST:

  
Jay Bennett, Recorder  
City Clerk

CITY OF DILLINGHAM, ALASKA

RESOLUTION NO. 2011-85

**A RESOLUTION OF THE DILLINGHAM CITY COUNCIL ACCEPTING THE FY 2013 CAPITAL IMPROVEMENTS PROGRAM**

WHEREAS, Dillingham Municipal Code 2.68.160 requires that the Dillingham Planning Commission prepare and recommend to the City Council an annual update of a Capital Improvements Program; and

WHEREAS, staff and the public prepared proposals from August 1 to 31, 2011; and

WHEREAS, the Planning Department received 37 nominations from staff and the public; and

WHEREAS, a Project Review Committee, comprising the Finance Director, the City Manager, the Public Works Director, the Planning Commission Chair, and the Planning Director reviewed the projects at staff and public workshops on September 6, 2011; and

WHEREAS, the PRC ranked the projects for feasibility, compliance issues, and other pertinent criteria on September 7, 2011; and

WHEREAS, September 8 through September 14, 2011, members of the Planning Commission ranked each of the projects based on the community values of impact on quality of life, health and safety, sustainability, and economic development; and


WHEREAS, the individual rankings were combined into one list for which the Planning Commission held a public hearing on September 20, 2011; and

WHEREAS, on September 20, 2011 the Planning Commission passed Resolution 2011-10, recommending a FY 2013 Capital Improvements Program to the City Council; and


NOW, THEREFORE, BE IT RESOLVED that the Dillingham City Council accepts the attached FY 2013 Capital Improvements Program.

PASSED and ADOPTED by the Dillingham City Council on December 1, 2011.

SEAL:

  
Alice Ruby, Mayor

ATTEST:

  
Janice Williams, City Clerk

# FY13 Capital Improvement Program

- 1 Snag Point Force Main Relocation
- 2 Library Roof
- 3 Water System Improvements 1.3 and 1.4
- 4 Snag Point Bulkhead Restoration
- 5 E 911 Critical System Replacement/upgrade
- 6 Emergency Bank Stabilization at Harbor
- 7 Wastewater Treatment Lagoon Outfall Relocation
- 8 South and East Harbor Bulkhead
- 9 Fire Station and Public Safety Building \*
- 10 Wastewater Lift Stations
- 11 Old Airport Sewer
- 12 Seward and D Street Rehabilitation
- 13 Senior Center Renovation
- 14 Wasterwater Treatment Plant Upgrades
- 15 Harbor Float Replacement
- 16 Territorial School Renovation
- 17 Utilities and Storm Sewer Upgrades
- 18 Evergreen Cemetery - build interior road, survey and lay out plots
- 19 Nerka Road Rehabilitation
- 20 New Hyster 1050 Fork Lift
- 21 Construct or Purchase Animal Shelter
- 22 Harvey Samuelsen Community Cultural Center
- 23 Warm Equipment Storage Addition
- 24 Roller Compactor
- 25 950 H Cat Loader
- 26 Brush Cutter, Sweeper, Snow blower
- 27 Fence around Public Works Storage Yard
- 28 Renovate City Hall
- 29 Hockey Rink Pavilion Planning and Design
- 30 Live Fire Training Facility
- 31 Case 580 M Extendahoe Backhoe

\* Note this list combines #9 and #11 Fire Station and Public Safety Building as item #9 from the original list adopted by the Planning Commission September 20, 2011 Attach to PRC Resolution 2011-10

**THE CITY OF DILLINGHAM PLANNING COMMISSION**

**RESOLUTION NO. 2011-10**

**A RESOLUTION OF THE DILLINGHAM PLANNING COMMISSION APPROVING THE  
FY13 CAPITAL IMPROVEMENTS PLAN**

WHEREAS, Dillingham Municipal Code 2.68.160 requires the Dillingham Planning Commission to prepare and recommend to the City Council an annual update of the Capital Improvements Plan (CIP); and

WHEREAS, staff and the public prepared proposals during the month of August; and

WHEREAS, the Planning Department reviewed 37 nominations from staff and the public; and

WHEREAS, a Project Review Committee consisting of the Finance Director, the City Manager, the Public Works Director, the Planning Commission Chairman, and the Planning Director, reviewed the projects at public workshops September 6 and 7; and

WHEREAS, the Planning Commission and PRC ranked the projects for urgency, as well as impact on quality of life, health and safety, sustainability, and economic development; and

WHEREAS, the Dillingham Planning Commission held a public hearing on the FY13 proposed CIP list at its regular meeting September 20;

THEREFORE, BE IT RESOLVED that the Dillingham Planning Commission recommends to the Dillingham City Council the "Fiscal Year 2013 Capital Improvements Plan."


**FY13 Capital Improvement Projects List**

1. **Snag Point Force Main Relocation**
2. **Library Roof**
3. **Water System Improvements 1.3 and 1.4**
4. **Snag Point Bulkhead Restoration**
5. **E 911 Critical System Replacement/upgrade**
6. **Emergency Bank Stabilization at Harbor**
7. **Wastewater Treatment Lagoon Outfall Relocation**
8. **South and East Harbor Bulkhead**
9. **Fire Station**
10. **Wastewater Lift Stations**
11. **New Public Safety Building**
12. **Old Airport Sewer**
13. **Seward and D Street Rehabilitation**

14. Senior Center Renovation
15. Wasterwater Treatment Plant Upgrades
16. Harbor Float Replacement
17. Territorial School Renovation
18. Utilities and Storm Sewer Upgrades
19. Evergreen Cemetery - build interior road, survey and lay out plots
20. Nerka Road Rehabilitation
21. New Hyster 1050 Fork Lift
22. Construct or Purchase Animal Shelter
23. Harvey Samuelsen Community Cultural Center
24. Warm Equipment Storage Addition
25. Roller Compactor
26. 950 H Cat Loader
27. Brush Cutter, Sweeper, Snow blower
28. Fence around Public Works Storage Yard
29. Renovate City Hall
30. Hockey Rink Pavilion Planning and Design
31. Live Fire Training Facility
32. Case 580 M Extindahoe Backhoe

APPROVED AND ADOPTED THIS 20<sup>th</sup> DAY OF September, 2011.

  
\_\_\_\_\_  
Paul Liedberg, Commission Chair

  
\_\_\_\_\_  
Acting Commission Clerk